

Site Specific Design, Inc.

1704 Rockwell Road
Abington, PA 19001



215-887-3730

Invoice

Date	Invoice #
2/26/2025	79367


Bill To
Upper Providence Township Attn: Kevin Matson, Sewer Authority 935 N. Providence Road Media, PA 19063

Ship To
Upper Providence Township 935 N Providence Road 610-566-5376 Media, PA 19063

Cust. PO #	Terms	Rep	Ship Date	Ship Via		Project
	Net 30	SGon	2/26/2025			

Qty	Item Code	Description	Price Each	Amount
		Replace DH429429 with new twp pump DH934082 James Tillilie (Upper Prov) 241 Foxcatcher Lane Media, PA 19063 Date of service Technician Sebastian Gonzalez Arrived on site to find panel not in alarm. But alarm breaker to panel was turned off. Once I flipped the breaker on the panel still didn't go into alarm. Performed meter readings and all readings to pump were bad. Switches giving off high numbers. I wasn't getting any amp draws. Lifted up lid to station to find station over flowing and EQDs were disconnected and sitting in the water. I pulled pump DH429429 and saw that pump was from 1/2012 went to upper Prov shed to grab customer new core DH00934082. Before installing new core into station I megged the cables to panel and readings came back bad. I informed Scott about the situation and I installed a temporary cable 150'. I also replaced the contactor in panel due to it making a loud buzz noise. Once I ran new temporary cable I installed new core into station and ran pump out of alarm. Performed my last		

OK TO PAY
KEVIN MATSON, PE,
OPERATIONS MANAGER


3/10/2025

All material remains the property of Site Specific Design until final payment.

Subtotal

Sales Tax (0.0%)

Total

Payments/Credits

Total Due

Site Specific Design, Inc.

1704 Rockwell Road
Abington, PA 19001



215-887-3730

Invoice

Date	Invoice #
2/26/2025	79367

Bill To
Upper Providence Township Attn: Kevin Matson, Sewer Authority 935 N. Providence Road Media, PA 19063

Ship To
Upper Providence Township 935 N Providence Road 610-566-5376 Media, PA 19063

Cust. PO #	Terms	Rep	Ship Date	Ship Via		Project
	Net 30	SGon	2/26/2025			

Qty	Item Code	Description	Price Each	Amount
		meter readings and everything checks out good. I also informed customer about the temporary cable and informed him to be careful with cable laying down in drive way.		
1	Service/Ins	Service Call & Inspection Fee	170.00	170.00
1	Labor-SGon	Labor rate for Sebastian	130.00	130.00
1	7104	PA 1476P01 Contactor Control Clip Motor 220v/240v (Alarm Panels & 2000 Series flat control bracket)	66.0025	66.00
1	ND0036G11	150' Cable 6 conductor	497.45	497.45

All material remains the property of Site Specific Design until final payment.

Subtotal \$863.45

Sales Tax (0.0%) \$0.00

Total \$863.45

Payments/Credits \$0.00

Total Due \$863.45

Returned checks will incur a \$25.00 surcharge. If at any time your account runs past due, all shipments may be held pending.