

Site Specific Design, Inc.

1704 Rockwell Road
Abington, PA 19001
(215) 887-3730




Invoice

Date	Invoice #
1/11/2024	73528

Bill To
Upper Providence Township Attn: Kevin Matson, Sewer Authority 935 N. Providence Road Media, PA 19063

Ship To
Upper Providence Township 935 N Providence Road 610-566-5376 Media, PA 19063

Cust. PO #	Terms	Rep	Ship Date	Ship Via		Project
	Net 30	PB	1/11/2024			

Qty	Item Code	Description	Price Each	Amount
<div><div>OK TO PAY KEVIN MATSON, PE, OPERATIONS MANAGER</div><div> 02/07/2024</div></div>		Repair DH496338 Carrie Cornew 104 Water Mill Ln Media PA 19063 Date of service 1/11/24 Technician Pat Brady Pat arrived on site and found pump DH496338 not in alarm but Continuously running and not pumping out all meter readings were correct Pump was running at 6.8 amps. Pulled pump for further evaluation and found suction housing was clogged with wipes and paper towels and the stator was torn. everything else checked out good. Cleaned out the station best I could replaced stator reinstalled pump pumped down and shut off at 6.1 amps pump is running correctly .		
		1 Service/Ins	170.00	170.00
		2 Labor-PB	130.00	260.00
		1 8203	92.6109	92.61

All material remains the property of Site Specific Design until final payment.

Subtotal \$522.61

Sales Tax (0.0%) \$0.00

Total \$522.61

Payments/Credits \$0.00

Total Due \$522.61

Returned checks will incur a \$25.00 surcharge. If at any time your account runs past due, all shipments may be held pending.