

# Site Specific Design, Inc.

1704 Rockwell Road  
Abington, PA 19001



215-887-3730

## Invoice

Date	Invoice #
5/25/2025	80724

Bill To
Upper Providence Township Attn: Kevin Matson, Sewer Authority 935 N. Providence Road Media, PA 19063

Ship To
Upper Providence Township 935 N Providence Road 610-566-5376 Media, PA 19063

Cust. PO #	Terms	Rep	Ship Date	Ship Via		Project
	Net 30	Jon M	5/25/2025			

Qty	Item Code	Description	Price Each	Amount
		Replace DH428164 with new twp pump DH00942273  Jim Pil (Upper Prov) 401 Steeplechase Drive Media, PA 19063  Date of service 5/25/25 Technician Jon McKee  Arrived on site, station was not actively alarming, however, station was full and filling into the dry well. Checked voltage, voltage OK. Readings to pump were bad. Pulled pump DH428164 for evaluation. Physical condition was poor, heavy amount of corrosion of the pump. Cutter wheel/armature was locking up with bearing noise. Retrieved UPPER PROV new pump from the UPPER PROV shed to replace early extreme pump. Installed new core DH00942273 and began testing. Alarm sounded OK. Pump turns on and off as required and evacuated at 5.8/5.9 amps at factory specifications		
1	Emergency	Emergency Weekend/After Hours Rate	200.00	200.00
1	Labor-Jon M	Emergency Labor-Jon M	225.00	225.00

**Subtotal** \$425.00

**Sales Tax (0.0%)** \$0.00

**Total** \$425.00

**Payments/Credits** \$0.00

**Total Due** \$425.00

Returned checks will incur a \$25.00 surcharge. If at any time your account runs past due, all shipments may be held pending.